



## *REPLACEMENT OF EXISTING WATERLINES IRWIN PLACE AND STURBRIDGE LANE, AMHERST, NY*

---



*Breaking rock on Sturbridge Lane*

**Owner:**

*Town of Amherst Engineering  
Department*

**Location:**

*Town of Amherst, New York*

**Completion Date:**

*Fall 2002*

**Construction Cost:**

*\$154,000*

**Services:**

- *Design of Project*
- *Construction Inspection*
- *Bid-Phase Services*
- *Construction Oversight*

Design services and Construction Oversight services were provided by Watts Engineers for the replacement of two waterlines in Amherst, New York. The existing 4-inch diameter pipes were replaced to increase flow for fire protection in these areas. Water services, valves, and hydrants were also upgraded.

Eight-inch ductile-iron pipe was used as the replacement pipe and the project was designed in accordance with Erie County Water Authority standards.

Bid Phase services and construction inspection services were also provided to the Town.